



The ERNAKULAM DISTRICT *Co-operative* BANK *Ltd.*

Head Office: P.B. NO. 4, P.O. KAKKANAD, Kochi - 682 030

Website : www.edcbank.com, E-mail : mail@edcbank.com

Phone : (PBX) 2424549, 2424613, 2424683, 2424684, 2424899, 2423684

Fax : 0484 - 2424584

AN ISO 9001 : 2015 CERTIFIED BANK

Painting and Roofing Works of Bank's Koothattukulam Branch Buildings

SHORT TENDER NOTICE

Sealed competitive Tenders in the prescribed form are invited from experienced contractors for undertaking the following works

Name of Work	: Painting and roofing works at Bank's Koothattukulam Branch Buildings
Period of Completion	: 15 Days
Availability of Tender Documents	: Take printout from bank website
Last Date & Time for Submission	: 18/11/2019 2 PM
Date & Time of Opening Tender	: 18/11/2019 3 PM

Further details regarding the tenders can be had from the Head Office of the Bank at Kakkanad during the office hours.

The undersigned reserve the right to accept or reject any one or all quotations received with or without assigning any reason.

Place: Kakkanad
Date : 12/11/2019



sd/-
Dy. General Manager

To Website
12/11

EDCB - KOOTHATTUKULAM BRANCH RENOVATION - ESTIMATE

SIN o	Particulars	No	L	B	H	Qty	Unit	Amount
1	Cleaning & Clearing small plants and waste from the roof top and walls of existing Bank building							
		LS						
2	Applying two coats of acrylic plastic emulsion paint,after cleaning and strapping the surface							
	Outside wall - overall	1	42.15		7.80	328.77		
	parapet wall	1	42.60		1.30	55.38		
	Inside - bank hall	1	59.90		3.60	215.64		
	Strong room	1	14.60		2.40	35.04		
	Dining	1	22.30		3.60	80.28		
	Latrin	1	8.60		3.60	30.96		
	Columns	2	0.50		0.25	0.25		
	beams	6	9.00		0.40	21.60		
	Ceiling	1	19.30		10.65	205.55		
	Front - GF	2	11.20		7.50	168.00		
	Outside - side wall	2	5.10		7.00	71.40		
	Stair-bottom	2	5.00		1.80	18.00		
						1230.87	M ²	
	Deductions							
	Strong room- door	1	1.50		2.20	3.30		
	Doors - D1	3	0.90		2.10	5.67		
	Windows W4	6	2.00		1.50	18.00		
	Ventilators	4	1.00		0.90	3.60		
	Rolling shutter	1	3.20		3.30	10.56		
						41.13	"	
	Total Less deductions					1189.74	M ²	
		Say	1190.0	M ²	@		/1M ²	
3	Roofing with G.I trafford profile coated 0.35mm (28 B.G) thick or nearest available thickness with overlaps of 150 mm at ends and GI hooks or crank bolts and nuts including plain washers and bitumen washers etc. complete.							
	Sun shade for Window	5	3.00	0.90		13.50		
	Sunshade for Ventilators	4	2.00	0.90		7.20		
						20.70	M2	
		Say	21	M2	@		/m2	

4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.						
	21	M2	9Kg/M2		189		
					189		
		Say	190	kg	@	/kg	
5	Painting with sythetic enamel paint two coats .after cleaning and rubbing the surface including all materials and labour charges, transportation and loading unloading, leading and lifting etc complete.						
	Rolling shutter	1	3.20	2.25	3.30	23.76	
	Rolling shutter	1	2.25	2.25	3.40	17.21	
	Collapsible shutter	1	3.20	2.25	3.30	23.76	
	Doors - D1	3	0.90	2.25	2.10	4.25	
	Windows W4	6	2.00	1	1.50	18.00	
	Ventilators	4	1.00	1	0.90	3.60	
	Long grill	1	10.65	1	2.35	25.03	
	Stair -grill	4	5.00	1	0.90	64.73	
						64.73	
		Say	65.00	M ²	@	/1M ²	
6	Supply and fixing roller blinds for windows and cabins including all costs etc. complete.						
	Windows W4	6	2.20		1.70	22.44	
	Manager Cabin	1	5.00		2.10	10.50	
						32.94	
		Say	33	M ²	@	/1M ²	
	Total						
	Unforseen item ifany						
	GRAND TOTAL						