



# *The* ERNAKULAM DISTRICT *Co-operative* BANK *Ltd.*

Head Office: P.B. NO. 4, P.O. KAKKANAD, Kochi - 682 030

Website : www.edcbank.com, E-mail : mail@edcbank.com

Phone : (PBX) 2424549, 2424613, 2424683, 2424684, 2424899, 2423684

Fax : 0484 - 2424584

AN ISO 9001 : 2015 CERTIFIED BANK

Dismantling and Reconstruction of Compound Wall for Bank's Property at Ernakulam

## SHORT TENDER NOTICE

Sealed competitive Tenders in the prescribed form are invited from experienced contractors for undertaking the following works

Name of Work	: Dismantling and Reconstruction of Compound Wall for Bank's Property at Ernakulam
Period of Completion	: 15 Days
Availability of Tender Documents	: Take printout from bank website
Last Date & Time for Submission	: 30/11/2019 2 PM
Date & Time of Opening Tender	: 30/11/2019 3 PM

Further details regarding the tenders can be had from the Head Office of the Bank at Kakkanad during the office hours.

The undersigned reserve the right to accept or reject any one or all quotations received with or without assigning any reason.

Place: Kakkanad

Date : 13/11/2019



sd/-   
General Manager

**ESTIMATE FOR DISMANTLING AND RECONSTRUCTION OF COMPOUND WALL FOR EDC PROPERTY AT ERNAKULAM**

SINo	Particulars	No	L	B	H	Qty	Unit	Amount
1	15.7.4 Demolishing brick/ Laterite masonry work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer in charge							
	Compound wall	1	29.00	0.20	1.20	6.96	m <sup>3</sup>	
	Total					6.96	m <sup>3</sup>	
	Say	6.96	m <sup>3</sup>	@	Rs.		/ 1m <sup>3</sup>	
2	5.2.3 Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20							
	Belt	1	36.00	0.40	0.15	2.16	m <sup>3</sup>	
	Total					2.16		
	Say	2.16	m <sup>3</sup>	@	Rs.		/ 1 m <sup>3</sup>	
3	5.9.5 Centering and shuttering including strutting, propping etc. and removal of form for : belts ,beams,lintel							
	Belt	2	36.00		0.15	10.80	m <sup>3</sup>	
	Total					10.80	"	
	Say	10.80	m <sup>3</sup>	@	Rs.		/ 1 m <sup>3</sup>	
4	5.22.6 Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete							
	Qty. Of concrete					2.16	m <sup>3</sup>	
	70 kg / m <sup>3</sup>					151.20	kg	
	Total					151.20	"	
	Say	151.20	kg	@	Rs.		/ 1 kg	
5	Laterite masonry CM 1:6 using departmental laterite including all cost etc complete							
	Compound wall	1	16.20	0.20	1.50	4.86	m <sup>2</sup>	
	Total					4.86	"	
	Say	4.86	m <sup>3</sup>	@	Rs.		/m <sup>3</sup>	
6	50.6.1.2 Cement solid block masonry with cm 1:6 using best quality solid blocks of size 40x20x15 cm including cost and conveyance etc. complete above plinth level upto floor -V level							
	Posts	12	0.30	0.20	1.50	1.08	m <sup>3</sup>	
	Compound wall	1	17.40	0.20	1.50	5.22	m <sup>3</sup>	
	Total					6.30	"	
	Say	6.30	m <sup>3</sup>	@	Rs.		/m <sup>3</sup>	
7	Plastering with cement mortar 1:4, 12 mm thick one coat and including cost of materials and labour charges etc. complete							
	Belt	1	36.00		0.70	25.20	m <sup>2</sup>	

	Compound Wall,Overall	1	33.40		3.20	106.88	"	
	Posts	12	0.60		1.50	10.80	"	
	Posts top	12	0.30		0.20	0.72		
	Total					143.60	"	
	Say	143.60	m <sup>2</sup>	@	Rs.		/ 1m <sup>2</sup>	
8	13.43.1 Applying one coat of waster thinnable cement primer of approved brand and manufacturd on wall surface : Water thinnable cement primer					143.60		
	Qty;as per item NO: 7					143.60		
	Total					143.60	M <sup>2</sup>	
	Say	143.60	m <sup>2</sup>	@	Rs.		/ 1m <sup>2</sup>	
9	13.60.1 Finishing walls with Premium Acrylic emulsion paint with silicone additives of required shade :New work (Two or more coats applied @ 3.84 kg/10 sqm).					143.60		
	Qty;as per item NO: 7					143.60		
	Total					143.60	M <sup>2</sup>	
	Say	143.60	m <sup>2</sup>	@	Rs.		/ 1m <sup>2</sup>	
<b>Total</b>								
<b>Unforseen</b>								
<b>Grand Total</b>								